

The WARD Team





Stacey Epps Vice President

Vlad Kaminsky, PE **Construction Manager**

Arnold Rubenstein, PE Traffic Engineer

> **Grace Webb, EIT** Civil Engineer

Hildaliza Espinal Office Engineer (Spanish Speaking)

Tory Man, LEP

Director of Environmental Services

> Dan Vill, PE Project Manager

James Nardozzi

Executive Director

Ronald Cassella

Vice President of Operations and Construction

Zach Keith

Project Manager

Project Purpose and Goals



Improve truck turning movements



Shorter Signal Queues



Improve pedestrian safety and accessibility



Utility Improvements




Streetscape Improvements



Reduce Crashes

Existing Site Map (Added after meeting)



Collision Diagram (Added after meeting)

Figure T-2: Collision Diagram

COLLISION DIAGRAM

MUNICIPALITY: ---INTERSECTION: Washington Ave


CITY: Waterbury


FILE: WATERBURY

PERIOD: 5 YEARS

FROM: 1/1/19 TO: 11/14/24

BY: APAUL DATE: 01/14/2025






Road Realignment Plan



Utility Upgrades: Water, Sanitary, and Storm Systems

- The existing water main, installed in 1907, will be replaced as part of the project to improve water service reliability and capacity for the project area.
 - A temporary bypass will be constructed to minimize disruptions to residents and local businesses during the replacement.
- The existing sanitary sewer, installed in 1887 & 2001, will be lined using CIPP to increase the lifespan of the existing system.
- The existing storm sewer, installed in 1949, will be upgraded to improve the system's capacity.
- Test pits will be conducted at the beginning of project to prevent unforeseen delays during utility installation.



Utility Relocation: What to Expect

- Residents can expect minimal to no interruptions in service during the relocation process.
- Timely coordination with utility providers will ensure smooth transitions and minimal inconvenience.
- Proposed relocations are outside the existing roadway, most relocation can proceed with minimal disruption to traffic.



Construction Schedule and Traffic Impacts

- Construction is set to begin in June 2025, with an anticipated completion date in July 2026.
- Detours will be established in areas affected by construction to ensure smooth traffic flow.
- Access to businesses will remain uninterrupted.
- General public will be notified of any detours through VMS signage at least 2 weeks prior to the start of any activities.
- The City will use its website to inform the public about upcoming detours and project updates.










Improving Intersection Safety and Turning Movements

WB-50 – EXISTING NORTHWEST CORNER

WB-50- PROPOSED NORTHWEST CORNER




Improving Intersection Safety and Turning Movements

WB-67 – EXISTING SOUTHEAST CORNER

SOUTH MAIN STREET

WB-67 - PROPOSED SOUTHEAST CORNER



Bus Shelter Enhancements





- ✓ Weather Protection
- ✓ Safety & ADA Accessibility
- Streetscape & Aesthetic Enhancements
- ✓ Improved Lighting
- Seating for Waiting Passengers

Bus Route 470 will include a stop at South Main Street @ Washington Avenue

